

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-20544-00-00

LEASE NAME Stremel

WELL NUMBER AB-1

 Ft. from S Section Line

660' Ft. from E Section Line

660' FNL
 SEC. 2 TWP. 18S RGE. 24W (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 1-26-88

Plugging Completed 2-2-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt. 3 Box 20-A
Great Bend, Kansas 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4415'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	326'	none
				5-1/2"	4413'	2226'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4365' and 5 sacks cement. Shot pipe @3520', 3005', 2810', 2702', 2600', 2404', 2226', pulled a total of 70 joints of 5-1/2" casing.
Plugged surface with 3 hulls, 15 gel, 75 cement, 10 gel, 1 hull, 8-5/8" plug and 150 cement, 60/40 pos, 6% gel. Plugging Complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso


Box 347

(Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1988

Irene Hoover
 Notary Public

My Commission Expires:



FEB 10 1988