

15-135-21990-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 2 Twp. 18S Rge. 24W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines _____

NW SW
Lease Owner Zenith Drilling, Inc.
Lease Name KRAUSE Well No. #1


Office Address Suite 505, Fourth Financial Center, Wichita,
Character of Well (Completed as Oil, Gas or Dry Hole) KS 67201
Dry Hole

Date Well completed March 22 1981
Application for plugging filed March 22 1981
Application for plugging approved March 22 1981
Plugging commenced March 22 1981
Plugging completed March 22 1981

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4420'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

T.D. @ 4420'
Set 1st Plug @ 900' with 65 sx.
Set 2nd Plug @ 360' with 30 sx.
Set 3rd Plug @ 40' Solid Bridge with 10 sx.
Rathole with 5 sx., 50-50 posmix, 6% gel.

Plug was down @ 10:00 a.m., 3/22/81.
State Pluggers - Marion Schmidt.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.



STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice President (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of March, 19 81

Suzanne M. Hofer
Suzanne M. Hofer Notary Public.

My commission expires 2/4/85



15-135-21990-0000

CONTRACTOR'S WELL LOG

OPERATOR:	Zenith Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	KRAUSE #1
LOCATION:	NW SW, Section 2-18S-24W Ness County, Kansas
SPUD DATE:	3/14/81
COMPLETION DATE:	3/22/81

0	342	Sand & Shale
342	354	Shale
354	1110	Sand & Shale
1110	1370	Cedar Hill Sand
1370	1654	Shale
1654	1690	Anhydrite
1690	3209	Shale
3209	3419	Shale & Lime
3419	3830	Shale
3830	4240	Shale & Lime
4240	4310	Lime
4310	4337	Shale & Lime
4337	4420	Lime
	4420	Rotary Total Depth

Spud @ 10:00 a.m., 3/14/81. Cut 345' of a 12 1/2" hole. Ran 9 jts. of 8 5/8" - 20# casing (tally 363') Set @ 344'. Cemented with 200 sx. of common 2% gel, 3% c.c. Cement did circulate. Plug was down @ 6:20 p.m., 3/14/81.

T.D. @ 4420' laying down drillpipe, preparing to plug. Set 1st Plug @ 900' with 65 sx. Set 2nd Plug @ 360' with 30 sx. Set 3rd Plug @ 40' Solid Bridge with 10 sx. Rathole with 5 sx. 50-50 posmix, 6% gel. State Plugger - Marion Schmidt. Plug was down @ 10:00 a.m., 3/22/81.

SAMPLE TOPS:

Anhydrite 1650'
B/Anhydrite 1694'


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KRAUSE #1, NW SW, Section 2-18S-24W, Ness County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 31st day of March, 1981.



Suzanne M. Hofer
Suzanne M. Hofer, Notary Public