


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County. Sec. 3 Twp. 18S Rge. (E) 24(W)

Location as "NE/CNW/SW" or footage from lines C NE SW
Lease Owner Beardmore Oil Inc.
Lease Name Haas "A" Well No. 1
Office Address 700 - 120 Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed October 3 1970
Application for plugging filed October 3 1970
Application for plugging approved October 3 1970
Plugging commenced October 3 1970
Plugging completed October 3 1970
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4390 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Clay		0	60'	8-5/8"	256'	
Shale		60'	256'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set first plug at 600' with 70 sacks;
second plug at 240' with 20 sacks;
third plug at 40' with 1/2 sack hulls
and 10 sacks cement. Plugging completed
at 9:30 p.m. October 3, 1970

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oilwell Cementing Inc.
Address Box 628, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Heber Beardmore (owner & operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the-log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
700 - 120 Bldg., Wichita, Kansas (Address)

Subscribed and sworn to before me this 6th day of October, 1970



7-13-71

Shirley Ann Jackson
Notary Public.

15-135-20369-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HAAS "A" #1
C NE SW Section 3-18S-24W
Ness County, Kansas

Commenced: September 21, 1970
Completed: October 3, 1970

OPERATOR - Beardmore Oil, Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	257	Clay and shale	Ran 8 joints of 8-5/8" casing, set @ 256' w/155 sacks cement.
257	989	Shale, sand and pyrite	
989	1000	Anhydrite	
1000	1070	Shale and red bed	
1070	1315	Sand	
1315	1626	Shale	
1626	1658	Anhydrite	
1658	1880	Shale and shells	
1880	3760	Shale and lime	
3760	4051	Lime	
4051	4123	Lime and chert	
4123	4390	Lime	
4390	TD		Dry and abandoned.

I, JAMES S. SUTTON, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE SW Section 3-18S-24W, Ness County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II

JAMES S. SUTTON, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 13 day of October, 1970, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires February 1, 1972

Barbara J. Layton

Barbara J. Layton, Notary Public

