

15-135-20639-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness _____ County. Sec. 3 Twp. 18S Rge. (E) 24W(W)

Location as "NE/CNW/SW" or footage from lines. C SE SE

Lease Owner George A. Reed

Lease Name Haas Well No. 1

Office Address 1223 Union Nat'l Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-30 19 72

Application for plugging filed 6-30 19 72

Application for plugging approved 6-30 19 72

Plugging commenced 6-30 19 72

Plugging completed 6-30 19 72

Reason for abandonment of well or producing formation No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4390 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	Surface	338'	8-5/8"	331'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 660', plug, 70 sx cement;
Fluid to 300', plug, 20 sx cmt;
Fluid to 40', plug, 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 1972
WICHITA, KANSAS
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.

Address 701 First Nat'l Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF _____, ss.
JAMES L. DONELSON (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson

701 First Nat'l Bldg., Wichita, Kansas (Address)

Subscribed and sworn to before me this 3rd day of July, 19 72

Ella Priess Notary Public.



15-135-20639-0000

DRILLERS' LOG

GEORGE A. REED
Haas No. 1
C SE SE, Sec. 3-18S-24W
News County, Kansas

Elev: 2347 K.B.

Commenced: 6-23-72
Completed: 6-30-72

Surface Casing: 331' of
8-5/8" cemented w/225 sx
cement, 3% cc. 6-23-72

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 338
Shale	338 - 992
Blaine Anhydrite	992 - 1003
Red Bed & Shale	1003 - 1640
Anhydrite-Stone Corral	1640 - 1669
Shale	1669 - 2045
Lime	2045 - 4390 T.D.

RECEIVED
STATE CORPORATION COMMISSION
JUL 5 1972
CONSERVATION DIVISION
Wichita, Kansas

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON

STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 3rd day of July, 1972.

My Commission Expires:
August 25, 1972

Ella Priess
Ella Priess, Notary Public

