

LEASE NAME Potter

WELL NUMBER 2

2200 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 4 TWP. 18 RGE. 24 (E) or (W)

COUNTY Ness

Date Well Completed \_\_\_\_\_

Plugging Commenced 11-23-92

Plugging Completed 11-23-92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Viking Resources, Inc.

ADDRESS 105 S. Broadway, Suite 1040, Wichita, KS 67202

PHONE# (316) 262-2502 OPERATORS LICENSE NO. 5011

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-12-92 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4399 RTD 1614 PBTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	269	8-5/8"	269	0
		0	1656	4-1/2"	1656	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

15 SX 60/40 POZ. 8% gel down back side pressured to 500# Pumped 135 SX 60/40 8% gel down 4-1/2 casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License STATE CORPORATION COMMISSION

Address P.O. Box 420, Ness City, KS 67560

RECEIVED  
 FEB 10 1993

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Viking Resources, Inc.


CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Shawn P. Devlin (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn P. Devlin

(Address) 105 S. Broadway, Suite 1040  
 Wichita, KS 67202



SUBSCRIBED AND SWORN TO before me this 9th day of February, 1993  
Paula R. Dunagan  
 Notary Public

MALLARD JV, INC.  
P. O. BOX 1009  
McPHERSON, KS 67460

D R I L L E R S    L O G

OPERATOR: Viking Resources, Inc.  
105 S. Broadway, Suite #1040  
Wichita, KS 67202-4224

WELL: Potter #2  
API #: 15-135-23,560-0000

COMMENCED: March 11, 1991

LOC: Appx. N/2 N/2 SE

COMPLETED: March 19, 1991

2200 FT. FSL, 1320 FT. FEL

TOTAL DEPTH: 4399 FT.

SEC. 4    TWP. 18    RGE. 24 W

ELEVATION: 2322 FT. GL, 2330 FT. KB

COUNTY: Ness

\*\*\*\*\*

STATUS: Set Casing - Mississippi Formation

Size Hole Drilled: 12-1/4" x 270'  
Surface Casing: 8-5/8" x 20# x 258.91' (6 jts.)  
Set at: 268.51'  
Cement: 150 sacks 60/40 Pozmix, 2% gel, 3% cc  
P.D.: 9:30 p.m. 3/11/91

Size Hole Drilled: 7-7/8" x 4399'  
Production Casing: 5-1/2" x 9.5# x 1656'  
Set at: 1656'  
Cement: 400 sacks 60/40 Pozmix, 6% gel, 1/4# floseal per sk  
P.D.: 5:15 p.m. 3/19/91

Drill Stem Test: 4  
Electric Log: yes

\*\*\*\*\*

CERTIFICATE

James H. Hess, Vice-President of Mallard JV, Inc., hereby certifies that this is a true and correct copy of the log of the following well, as reflected by the files of Mallard JV, Inc.: Potter #2

*James H. Hess*  
James H. Hess, Vice-President

STATE OF KANSAS    )  
COUNTY OF McPHERSON    ) ss.

Subscribed and sworn to before me this 4th day of April, 1991.



*Bryan K. Hess*  
Bryan K. Hess, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1992

CONSERVATION DIVISION  
Wichita, Kansas