



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Norman Cook of H-30-Dulling Inc has this date requested permission to plug the following described well:

Operator's Full Name: Kansas Oil Corporation

Complete Address: 555 North Woodlawn - Wichita, Kansas 67202

Lease Name: Iserr Well No. #1

Location: NW-NE-NE Sec. 13 Twp. 20 Rge. 21 (W)

County: Mass Total Depth: 4422 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Cook was instructed to plug the well as follows:

- 8 5/8" 292 FT SR. CUC w/ 175ST Common - 2% Gel. - 3% Ca-cl.
- Order 110ST 50/50 Pozmix 6% Gel. + 8 5/8" Plug.
- spot with drill stem - with heavy mud between all plugs.
- 1ST Plug @ 720 FT w/ 70ST amt.
- 2ND Plug @ 270 FT w/ 25ST amt.
- 3RD Plug - solid bridge - plugs @ 40 FT w/ 10ST amt.
- 5th In Cat Hole

Very truly yours,

By Hal Hunter
COMMISSION

Marion Schmitt
Conservation Division Agent

DEC - 2 1980
CONSERVATION DIVISION
Wichita, Kansas