

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1976

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Conway of Slawson Drlg. has this

date requested permission to plug the following described well:

Mr. Conway guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name: Toadvine "A" Well No. 1

Location: SE SE NE Sec. 18 Twp. 18 Rge. (E)(W) 26

County: Ness Total Depth 4675' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Conway was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 800' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Res. Massey
Conservation Division Agent