



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co., Inc. has this

date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Castor Well No. B-1

Location: NE-NW-NW Sec. 17 Twp. 18 Rgs. (E)(W) 26

County: Ness Total Depth 4650' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

296'--8 5/8" Surface casing, cement circulated.

Circulate hole with heavy mud. Pull DP to 750' and displace 70 Sx.

cement thru DP. Pull DP to 270' and displace 30 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

Very truly yours,

M. L. Dike
Conservation Division Agent