

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1959

CONSERVATION DIVISION
Wichita, Kansas

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date Sept 27, 1959, authorized the following plugging operation:

Operator's Full Name: A J Greenbaum

Complete Address: 560 Fourth "atl Bld Wichita, Kansas

Lease Name: Watson Well No. 1

Location: ne ne ne Sec. 35 Twp. 18 Rge. 26 (E) (W)

County: Ness Total Depth: 4415

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits circulate hole with heavy mud, set cementing plug at 600 ft.
and displace 20 sac cement thru drill pipe, heavy mud to 240 ft.
set cementing plug and displace 20 sac cement, heavy mud to 40 ft.
set and tie cementing plug in place, dump 1/2 sac hulls, and displace
10 sac cement cementing to base of cellar.

Very truly yours, Gilbert P. Leiker

Signed: Gilbert P. Leiker
Conservation Division Agent