

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 19 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Dunigan Operating Company, Incorporated,

Complete Address: P. O. Box #261, Pampa, Texas.

Lease Name: Reeves Well No. 1

Location: SW-NE Sec. 32 Twp. 18 Rge. (E)(W) 26

County: Ness Total Depth 4569' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

347'--8 5/8" Surface casing, cement circulated with 200 Sx.
Circulate hole with heavy mud. Pull DP to 720' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 300' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

H. L. Dehels
Conservation Division Agent