

15-135-20369-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beardmore Oil Inc.
Complete Address 700 One Twenty Bldg., Wichita, Kansas
Lease Name Hans Hays "A" Well No. 1
Location C NE SW Sec. 3 Twp. 18 Rge. (E) (W) 24
County Ness Total Depth 4390
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Gabbert - Jones
Address Wichita, Kansas License No.
Operation Completed: Hour 9:30 P Day 3 Month 10 Year 1970

The above well was plugged as follows:

RTD 4390' 8 5/8 csg set at 256' cwc Cmt. Mat. 50-50 poz W/6% total gel
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2-sk-hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 10-5-70

INV. NO. 2617-W