

15-135-20639-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

JUL 3 1972

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name DNE Drilling, Inc. & George Reed  
Complete Address 1223 Union National Bldg., Wichita, Kansas  
Lease Name Haas Well No. 1  
Location C SE SE Sec. 3 Twp. 18 Rge. (E) (W) 24  
County Ness Total Depth 4390'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor DNE Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 6 A Day 30 Month 6 Year 1972

The above well was plugged as follows:

RTD 4390' 8 5/8 csg set at 338' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: John A. Measey  
Well Plugging Supervisor

INVOICED

DATE 7-5-72

INV. NO. 5972-00