

15-135-28638-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 12 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beardmore Oil, Inc.

Complete Address 700 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Elting Well No. 1

Location SW NE Sec. 4 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4351'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 12 N Day 9 Month 12 Year 1972

The above well was plugged as follows:

Total Depth 4351' 8 5/8 csg set at 258' cwc 175 sk.

5 1/2 csg set at 4342' cw 75 sk cmt.

Filled 5 1/2 csg W/sd (4300-4351) Damped 5 sk cmt W/dump bailer. (526504300)

Cutoff and recovered 2411' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -70 sk cmt -8 sk

gel & water -released 8 5/8 plug and pumped 70 sk cmt. (Sun Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 12/12/72
INV. NO. 6713-W