

15-135-20772-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1973

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name DNB Drilling, Inc. & G. A. Reed
Complete Address 1223 Union National Bldg., Wichita, Kansas
Lease Name Rufenacht Well No. 1
Location C NW SW Sec. 11 Twp. 18 Rge. (E) (W) 24
County Ness Total Depth 4395'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 3 P Day 29 Month 6 Year 1973

The above well was plugged as follows:

RTD 4395" 8 5/8 csg set at 326' cwc: 200 sk. Cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

7/2/73

INV. NO.

7579-W

Signed:

Well Plugging Supervisor

Leo F. Massey