

15-135-20486-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling & Petroleum Resources

Complete Address Box 18407 Wichita, Kansas

Lease Name Leiker Well No. 2

Location A/ SE SE Sec. 12 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4336'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dunne & Gardner Petroleum

Address Wichita, Kansas License No.

Operation Completed: Hour 9:15 P Day 3 Month 10 Year 1971

The above well was plugged as follows:

RTD 4336' 8 5/8 csg set at 335' cwc 235 sk Cmt Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 300', set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 10-12-71

INV. NO. 4449-W