

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 18407 Wichita, Kansas 67218

Lease Name Leiker Well No. 1

Location C NW SE Sec. 12 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4355'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:30 A Day 26 Month 10 Year 1973

The above well was plugged as follows:

Total Depth 4355' 8 5/8 csg set at 329' cwc 200 sk.

5 1/2 csg set at 4346' cw 150 sk cem.

PBTD 4300' & perf. (4111-4123)

Set 5 1/2 wood plug at 4000' - poured 10' sd - dumped 5 sk cmt W/dump bailer. (3950-4000)

Cutoff and recovered 2200' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls - 70 sk cem. - 5 sk gel & water - sand capped with 20 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 10/30/73

INV. NO. 8085-W