

15-135-20396-00-00

~~KANSAS~~

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 97 Ellinwood, Kansas 67526

Lease Name Levan "A" Well No. 1

Location C NW NE Sec. 12 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4410'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 A Day 12 Month 7 Year 1974

The above well was plugged as follows:

Total Depth 4410' 8 5/8 csg set at 331' cwc 200 sk.

5 1/2 csg set at 4408' cw 100 sk cmt.

5 1/2 csg PBD 4378' with top perf. (4352)

Filled 5 1/2 csg with sd (4378-4300) dumped 5 sk cmt with dump bailer. (4300-4270)

Cutoff and recovered 82 jts. App. 2625' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/100 lbs hulls -70 sk cmt - 8 sk

gel & water -released 8 5/8 plug and pumped 60 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing
Well Plugging Supervisor

INVOICED

DATE 7/16/74

INV. NO. 9523-W