

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.

Complete Address Box 18407 Wichita, Kansas 67218

Lease Name Levan "A" Well No. 2

Location C SW NE Sec. 12 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4352'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Company

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2 P Day 25 Month 1 Year 1974

The above well was plugged as follows:

Total Depth 4352' 8 5/8 csg set at 347' cwc 250 sk.

5 1/2 csg set at 4331' cw 100 sk cem.

Filled 5 1/2 csg W/sd (4300-4352) dumped 4 sk cmt W/dump bailer. (4270-4300)

Cutoff and recovered 2733' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs hulls -70 sk 50-50 poz 6% gel-

10 sk gel & water -released 8 5/8 plug and pumped 50 sk 50-50 poz 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey  
Well Plugging Supervisor

INVOICED

DATE 1/30/74

INV. NO. 8459-W