

15-135-20778-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 9 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling

Complete Address Box 18407 Wichita, Kansas

Lease Name Anspaugh Well No. 2

Location C S/2 SE SW Sec. 12 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4441'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dunne-Gardner Petro.

Address Wichita, Kansas License No.

Operation Completed: Hour 7 A Day 8 Month 8 Year 1973

The above well was plugged as follows:

RTD 4441' 8 5/8 csg set at 339' cwc 250 sk. Cmt Mat. 50-50 poz cmt W/6% gel.
Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. F. Messers
Well Plugging Supervisor

INVOICED

DATE 8/9/73
INV. NO. 7744-U