

15-135-20092-0000

Form CP-3
Rev. 6-26-62

KANSAS

J.P.

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1967
12-11-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Mack Oil Co.

Complete Address: 812 Union Center Bldg. Wichita, Kansas

Lease Name Schuler Schuler Well No. 1

Location C NW NW Sec. 15 Twp. 18 Rge. 24 (E) (W) X

County Ness Total Depth 4370

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 1 P Day 7 Month 12 Year 1967

The Above well was plugged as follows:

RTD 4370' 8 5/8 csg set at 398' cwc 200 sc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 360' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

Used 100 sc 50-50 poz cement with 6% gel. (135 cu. Ft.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 12/11/67
INV. NO. 6878-W