

15-135-20414-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Derrick - American Oil, Inc.

Complete Address 355 R. H. Garvey Bldg., Wichita, Kansas

Lease Name Rupp Well No. 1

Location N/2 NW SE Sec. 17 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4562

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Gabbert - Jones

Address Wichita, Kansas License No.

Operation Completed: Hour 10:15A Day 24 Month 2 Year 1971

The above well was plugged as follows:

RTD 4562' 8 5/8 csg set at 293' cwc Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 3/2/71
INV. NO. 3399-W