

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1978
4-11-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -135-21335-0000 (of this well)

Operator's Full Name A. Scott Ritchie

Complete Address Suite 950-125 North Market, Wichita, Kansas 67202

Lease Name Stenzel Well No. 1

Location C SE SE Sec. 17 Twp. 18 Rge. (E) (W) 24

County Ness Total Depth 4367'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 11 A Day 10 Month 4 Year 1978

The above well was plugged as follows:

Total Depth 4367' 8 5/8 csg set 293' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.

4 1/2 csg set 4366' cw 100 sk cem. Top perf. (4316'-4310')

Filled 4 1/2 csg with sand (4366'-4290') dumped 3 sk cem W/dump bailer. (4290'-4260')

Cutoff & recovered 3320' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs

hulls-followed with 70 sk 50-50 poz 2% -displaced with 6 sk gel & water & capped

with cementing plug & 70 sk 50-50 poz 2% & shutin. FPP 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-11-78

INV. NO. 7091-W