

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1976

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-135-20827-0000 (of this well)

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Walters Drilling Company
Complete Address 400 Insurance Bldg., Wichita, Ks. 67202
Lease Name Litchfield Well No. 1
Location C SW SW Sec. 28 Twp. 18 Rge. (E) (W) 24
County Ness Total Depth 4373'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Co. Tools by Allied Cementing Co.
Address _____ License No. _____

Operation Completed: Hour 11 A Day 9 Month 6 Year 1976

The above well was plugged as follows:

Total Depth 4373' 8 5/8 csg set at 242' cwc 175 sk.

5 1/2 csg set at 4372' cw 150 sk cem.

5 1/2 csg PBD 4360' with Perf. (4332'-4340')

5 1/2 csg 2-stage at 1326' cwc. No pipe recovered.

Mixed & pumped down 5 1/2" csg with 25 sk cem. W/100 lbs hulls displaced with

30 sk gel & water & capped with 50 sk cem. by Allied Cementing Co. PP 1200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 6/10/76

INV. NO. 3327-W