

15-135-20350-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*12*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 7 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Palomino Petroleum & Acme Oil  
Complete Address 304 Insurance Bldg., Wichita, Kansas 67202  
Lease Name Cranston Well No. 1  
Location C SE SE Sec. 28 Twp. 18 Rge. (E) (W) 24  
County Ness Total Depth 4345  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Hellar Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 5:15 A Day 5 Month 7 Year 1970

The above well was plugged as follows:

RTD 4345' 8 5/8 csg set at 230' cwc Cmt. Mat. 100 sk reg. poz 6% gel  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 220' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 7/7/70  
INV. NO. 2180-W