

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 10 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Thor Corp  
Complete Address: Box 987 Great Bend, Kansas  
Lease Name Thompson Well No. 2  
Location W $\frac{1}{2}$  SE SE Sec. 14 Twp. 18 Rge. (E) (W) 26  
County Ness Total Depth 4446  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Ace Pipe Pulling Co  
Address: Great Bend, Kansas License No. 2  
Operation Completed: Hour 2PM Day 7 Month 6 Year 63

The Above well was plugged as follows:

13" 76' circulated with cement - 5 $\frac{1}{2}$ " 4435' cement ? - squeezed in  
Dakota section at 1276' with cement.

Filled with sand to 4425', set 4 sax cement with dump bailer - pulled  
809' 5 $\frac{1}{2}$ " to 500', circulated hole with heavy gel mud through 5 $\frac{1}{2}$ " -  
displaced 30 sax cement through 5 $\frac{1}{2}$ " at 500'; heavy mud to 180',  
displaced 30 sax cement through 5 $\frac{1}{2}$ " at 180', heavy mud to 20',  
cement 20' to 0'

Mudding and cementing by Ace Pipe Pulling pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edson Peety  
Well Plugging Supervisor

DATE 6/11/63

INV. NO. 4333-4