

15-135-20271-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th National Bank Building Wichita, Kansas

Lease Name Betz "H" Well No. 1

Location C SE NW Sec. 16 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4500'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 9:15P Day 3 Month 8 Year 1969

The above well was plugged as follows:

RTD 4500' 8 5/8 csg set at 268' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/5/69

INV. NO. 244-W

Signed: Leo F. Mearns
Well Plugging Supervisor