

15-135-20990-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
FEB 5 1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Delta Western & G. Reed

Complete Address Suite 645, Fourth Financial Center, Wichita, Kansas

Lease Name Iserm Well No. 1

Location C SE NE Sec. 13 Twp. 20 Rge. (E) (W) 21

County Ness Total Depth 4450'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XXX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12 N - Day 4 Month 2 Year 1975

The above well was plugged as follows:

RTD 4450' 8 5/8 csg set at 283' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Les F. Massey
Well Plugging Supervisor

DATE 2/5/75

INV. NO. 789-W