

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21,241 - 0000 (of this well)

Operator's Full Name Donald C. Slawson

Complete Address 408 One Twenty Bldg., Wichita, Kansas

Lease Name Toadvine "A" Well No. 1

Location SE SE NE Sec. 18 Twp. 18 Rge. (E) (W) 26

County Ness Total Depth 4675'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 10:45 A Day 23 Month 8 Year 1976

The above well was plugged as follows:

RTD 4675' 8 5/8 csg set 278' cwc 200 sk. Plg. Mat. 50-50 poz 6%.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1976

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: *L. W. Massey*
Well Plugging Supervisor

INVOICED

DATE 8/27/76

INV. NO. 3703-W