

15-135-21167-0000

R

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAR 01 1976

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson

Complete Address 408 120 Bldg., Wichita, Kansas

Lease Name Caster "E" Well No. 1

Location SW <sup>NE</sup> SE Sec. 17 Twp. 18 Rge. (E) (W) 26

County Ness Total Depth 4602'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Co. Tools

Address      License No.     

Operation Completed: Hour 6:35 A Day 28 Month 2 Year 1976

The above well was plugged as follows:

RTD 4602' 8 5/8 csg set 354' cwc 275 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3-2-76

INV. NO. 2826-W

Signed: Leo Massey  
Well Plugging Supervisor