

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

JUL 2 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Cimarron Oil Co  
Complete Address: Box 1142 Liberal, Kans  
Lease Name Selsor Well No. 1  
Location CNE NE Sec. 6 Twp. 18 Rge. (E) (W) 26  
County Ness Total Depth 4565  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated: \_\_\_\_\_  
Plugging Contractor: Bob Sargent Casing Pulling  
Address: \_\_\_\_\_ License No. 511  
Operation Completed: Hour 4PM Day 30 Month 6 Year 65

**The Above well was plugged as follows:**

8 5/8" 268' circulated with cement - 4 1/2" 4565 cement 3824'  
~~FB to 5947' Perf 5897'~~  
Pumped 10 sax cement on bottom top cement at 2800' -  
Pulled 2710' 4 1/2" to 768' & circulated hole with heavy gel mud through 4 1/2"  
at 768' - displaced 20 sax cement through 4 1/2" at 700', heavy mud to  
240', displaced 20 sax cement through 4 1/2" at 240', heavy mud to 35', set  
10 sax cement to bottom cellar.

Mudding and cementing by Sargent Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 7/2/65  
INV. NO. 1400-W

Signed: Evan Perry  
Well Plugging Supervisor

**INVOICED**