

15-135-19125-0000

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION

OCT 29 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Amerada Pet Corp

Complete Address: Box 197 Great Bend, Kansas

Lease Name D. V. Smith Tract Well No. 1

Location CSW NW Sec. 5 Twp. 18 Rge. (E) (W) 26

County Ness Total Depth 4540

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith

Address: Ellinwood, Kans License No. 396

Operation Completed: Hour 4PM Day 22 Month 10 Year 64

The Above well was plugged as follows:

8 5/8" 350' circulated with cement - 4 1/2" 4540' -

Sand back to 3350', set 5 sax cement with dump bailer - pulled 4 1/2" to 700' circulated hole with heavy gel mud through 4 1/2" at 700' (28 sax Gel) displaced 20 sax cement through 4 1/2" at 700', heavy mud to 240', displaced 20 sax cement through 4 1/2" at 240', heavy mud to 35', capped with 10 sax cement.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

DATE 10/29/64Signed: E. J. Petty
Well Plugging SupervisorINV. NO. 116-11