

15-135-20954-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tomlinson Oil Company, Inc.

Complete Address 200 West Douglas, Wichita, Kansas 67202

Lease Name Reeves Well No. 1

Location 100' S/C SW NE Sec. 32 Twp. 18 Rge. (E) (W) 26

County Ness Total Depth 4503'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11 A Day 8 Month 1 Year 1975

The above well was plugged as follows:

Total Depth 4503' 8 5/8 csg set at 347' cwc 225 sk. Plg. Mat. comm cement.5 1/2 csg set at 4502' cw 275 sx cem.Filled 5 1/2 csg W/sd (4503-4475) dumped 4 sx cem W/dump bailer. (4475-4445)Cutoff & recovered 2643' of 5 1/2 csg.Mixed & pumped down 8 5/8 csg with 20 sk gel & water -released plug & pumped 80 sx cement -displaced with 6 sk gel & water -& capped with 20 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging SupervisorDATE 1/10/75
INV. NO. 634-W