

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20836-00-00
Spot: N2N2NE Sec/Twnshp/Rge: 19-27S-25W
82 feet from N Section Line, 1459 feet from E Section Line
Lease Name: SCHNEWEIS-TURLEY Well #: 1
County: FORD Total Vertical Depth: 5230 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	353		WITH 230 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/30/2012 2:30 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: SCOTT EDWARDS Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1690' WITH 50 SX CMT. 2ND PLUG AT 860' WITH 80 SX CMT. 3RD PLUG AT 380' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 08/30/2012 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1690' WITH 50 SX CMT. 2ND PLUG AT 860' WITH 80 SX CMT. 3RD PLUG AT 380' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

RECEIVED
SEP 10 2012
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

SEP - 5 2012

KCC DODGE CITY

Signed

Richard M. Lacey
9/20/12

(TECHNICIAN)

AGN