

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22357-00-00
Spot: SESWSENE Sec/Twnshp/Rge: 10-26S-11W
2317 feet from N Section Line, 978 feet from E Section Line
Lease Name: GRIEVE TRUST Well #: 1-10
County: PRATT Total Vertical Depth: 4604 feet

Operator License No.: 34457

Op Name: ADAMS RESOURCES EXPLORATION C

Address: PO BOX 844
HOUSTON, TX 77001

String	Size	Depth (ft)	Pulled (ft)	Comment
<i>ORP.</i> CIBP		4035		WITH 2 SX CMT
PROD	5.5	4228	0	WITH 250 SX CMT
SURF	8.625	365		WITH 300 SX CMT

Well Type: OG

UIC Docket No:

Date/Time to Plug: 09/10/2012 10:30 AM

Plug Co. License No.: 5893

Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: DAVID EHLER

Company: ADAMS RESOURCES

Phone: (979) 777-8094

Proposed Plugging Method: SET CIBP @ 4035' & 2 SX CMT. PERFORATE @ 630'. PUMP CMT DONW 5 1/2" & CIRCULATE TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS. *W*

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/10/2012 12:50 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

CIBP @ 4035' WITH 2 SX CMT. CASING WAS PRESSURED TESTED TO 500# FOR 20 MINUTES. PERFORATED @ 630'. PUMPED 200 SX CMT DOWN THE 5 1/2" CASING CIRCULATING CMT UP THE 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4042	4086		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

RECEIVED
SEP 20 2012
KCC WICHITA

District: 01

Signed *Eric MacLaren*
9/20/12 (TECHNICIAN)

RECEIVED
SEP 14 2012
KCC DODGE CITY *MP*