

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-20998-00-01
Spot: N2N2SW Sec/Twnshp/Rge: 31-23S-17E
1145 feet from S Section Line, 4620 feet from E Section Line
Lease Name: TIDD Well #: 3
County: WOODSON Total Vertical Depth: 940 feet

Operator License No.: 8210
Op Name: BIRK, EDWARD E.
Address: 302 S 16TH ST
BURLINGTON, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.5	939		
PROD	2.875	940		100 SX
SURF	7	40		10 SX
SURF	7	41		

Well Type: EOR UIC Docket No: E30127.1 Date/Time to Plug: 03/07/2012 12:00 AM
Plug Co. License No.: 8210 Plug Co. Name: BIRK, EDWARD E.
Proposal Rcvd. from: EDWARD E BIRK Company: Phone: (620) 364-1311

Proposed Plugging Method: Set solid plug from TD to surface using 60 sx cement.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 03/07/2012 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe inside the 2.875" casing to TD. Pumped cement through the 1" pipe inside the 2.875" casing at TD. Pulled 20 joints of 1" pipe and continued pumping cement. Pulled 10 joints of 1" pipe and pumped cement to surface. Pulled 5 joints of 1" pipe and circulated cement to surface. Pulled rest of the 1" pipe and topped the well off with cement. A total of 160 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
916	919		
RECEIVED			
SEP 18 2012			
KCC Chanute Dist. #3			
RD			
RECEIVED			
SEP 20 2012			
KCC WICHITA			

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)