

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05063-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 1-20S-6W
1653 feet from S Section Line, 2981 feet from E Section Line
Lease Name: BRADEN B Well #: 5
County: RICE Total Vertical Depth: 3343 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3322	870	75 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2012 9:00 AM
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.
Proposal Rcvd. from: TERRY P BANDY Company: TE PE OIL & GAS Phone: (620) 628-4428

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/11/2012 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3213' AND CAP WITH 5 SX'S CEMENT. TAGGED CEMENT @ 3165' ON 9-10-12. CUT CASING AT 870', AND PULL TO 850' AND PUMP 35 SX'S CEMENT, PULL CASING TO 450' AND PUMP 35 SX'S, PULL CASING TO 250' AND CIRCULATE TO SURFACE. PULL CASING OUT AND TOP OFF. USED APPROX. 165 SX'S ON TOP PLUGGING.

Perfs:

Top	Bot	Thru	Comments
3323	3343	OH	

RECEIVED
SEP 24 2012
KCC WICHITA

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #5670. RETURNED TA TO OPERATOR -MISSING INFO.

Plugged through: CSG

District: 02

Signed Virgil Clothier
9/29/12 (TECHNICIAN)