

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name R. P. Nixon Operations, Inc.  
Complete Address Box 589 Russell, Kansas 67665  
Lease Name Reeves "A" Well No. 1  
Location NE NW ~~WNE~~ Sec. 29 Twp. 18 Rge. (E) (W) 26  
County NESS Total Depth 4571  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Pipe Pullers, Inc  
Address Box 486 Ellinwood, Kansas License No. 462  
Operation Completed: Hour 4 P Day 18 Month 11 Year 1970

The above well was plugged as follows:

Total Depth 4571' 8 5/8 csg set at 315' cmt 175 sk.  
5 1/2 csg set at 4568' cw 100 sk cmt.  
Filled 5 1/2 csg w/sd (4550-4571) Dumped 5 sk cmt w/dump bailer. (4510-4550)  
Cutoff and recovered 2745' of 5 1/2 csg.  
Pumped thru 8 5/8 plug container with 30 sk gel - 3 sk hulls - 100 sk poz 6% -  
13 bbl. water - plug and 20 sk poz 6%.  
Cmt (0-100) water (100-300) cmt (300-650) gel (650-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 11/20/70  
INV. NO. 2890-U