

15-165-20416-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Y* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 6 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson  
Complete Address 408 One Twenty Bldg., Wichita, Kansas  
Lease Name Oelkers "A" Well No. 1  
Location NE SW SW Sec. 17 Twp. 16 Rge. (E) (W) 19  
County Rush Total Depth 3942'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor        Co. Tools         
Address        License No.         
Operation Completed: Hour 3:30 P Day 1 Month 12 Year 1971

The above well was plugged as follows:

RTD 3942' 8 5/8 csg set at 438' cwc Cmt. Mat. 50-50 poz W/4% added gel.  
Gunned pits, circulated heavy mud, set cementing plug at 680' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 420' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

*W. G. ...*  
Date 12/7/71  
INV. NO. 4783-W

Signed: *Paul F. Masey*  
Well Plugging Supervisor