

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Monarch Oil & Gas Co.

Complete Address: 1429 Wichita Plaza Wichita, Kansas

Lease Name Littler Well No. 1

Location SE SW NW Sec. 28 Twp. 16 Rge. 19 (E) (W) X

County Rush Total Depth 3860'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated:       

Plugging Contractor: Sage Drlg.

Address: Wichita, Kansas License No.       

Operation Completed: Hour 5P Day 27 Month 6 Year 1968

The Above well was plugged as follows:

RTD 3860' 8 5/8 csg 258' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 7-2-68  
INV. NO. 8040-W

RECEIVED  
STATE CORPORATION COMMISSION  
Signed: Geo. Z. Murray  
Well Plugging Supervisor  
JUL 1 1968  
CONSERVATION DIVISION  
Wichita, Kansas