

R

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

3-23-76

API Number 15 - 165 - 20,561 - 0000 (of this well)

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas

Lease Name Oelkers Well No. 1

Location SW NW SE Sec. 17 Twp. 16 Rge. (E) (W) 19

County Rush Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 2:45 A Day 21 Month 3 Year 1976

The above well was plugged as follows:

RTD 3890' 8 5/8 csg set 251' cwc 200 sk. Plg. Mat. 50-50 pos 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 500' thru drill pipe.

Heavy mud to 250' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geoff. Massey
Well Plugging Supervisor

DATE 3-29-76

INV. NO. 2950-W