

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135 -22,564 -0000

C NW NW, Sec. 5, T 18 S, R 26 W/1

660 feet from N section line

660 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Lease Name Smith Well # 1

Operator: VAC Petroleum
Name & 6225 East Kellogg
Address Wichita, KS 67208

County Ness

Well Total Depth 4577 feet 148.75

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling License Number 5829

Address P. O. Box 18611

Company to plug at: Hour: 6:00 pm Day: 28 Month: April Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Rex Lueef

(company name) Aldebaran (phone) 16-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1950' with 50 sx cement

2nd plug at 960' with 60 sx cement

3rd plug at 360' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement

7th plug to circulate mousehole with 10 sx cement Signed Blaise Wiley

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00 pm Day: 28 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1950' with 50 sx cement, 2nd plug at 960' with 60
sx cement, 3rd plug at 360' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with
15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
MAY 07 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed Blaise Wiley
(TECHNICIAN)

INVOICED

DATE 5-10-84

INV. NO. 1456