

1 079232

80 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,011-0000  
C SE NW, SEC. 31, T 18 S, R 26 W/E  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9121

Lease Name Lamoree Well # 1

Operator: Kiwanda Resources

County Ness 149.53

Name & Address Box 7265, 200 E. 1st, Suite 500

Well Total Depth 4601 feet

Wichita, KS 67207

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Plains, Inc. License Number 4072

Address P.O. Box 346, NO. 283 Hwy, Ness City

Company to plug at: Hour: 1:45 p.m. Day: 6 Month: 10 Year: 1986

Plugging proposal received from Clint Base

(company name) Plains, Inc. Well Service (phone) 913-798-3995

were: 4 1/2" at 4599' PBDT 4550' Perfs 4166-76', 4524-30'

1st plug solid bridge at 4130' - sand back to 4120 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, and 1 sx hulls, release plug and pump 125 sx cement

Plugging Proposal Received by Don Ubel and Jack Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 p.m. Day: 6 Month: 10 Year: 1986

ACTUAL PLUGGING REPORT 1st plug solid wood plug at 4140', sanded back to 4130' and dumped 4 sx cement on top of sand through bailer

2nd plug squeezed well with 200 lbs. hulls, 10 sx gel, 50 sx cement, 15 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug, and pump 125 sx cement.

1 0 1986

Maximum pressure 350 psi and shut in 100 psi.

Remarks: Recovered 2270' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 10-13-86

Signed Dan Gooden  
(TECHNICIAN)

INV. NO. 15143  
10-6