

1 070264

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6759

Operator: William N. Bucklin III
Name & Address 150 California Street, Suite 300
San Francisco, CA 94111

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KS State Bank Bldg., Wichita, KS 67202

Company to plug at: Hour: 6:20 p.m. Day: 11 Month: 12 Year: 19 86

Plugging proposal received from Bruce Fickel

(company name) Red Tiger Drilling Company (phone) 913-625-7821

were: _____ to fill hole with heavy mud and spot cement through drill pipe. Elevation 2589'
Anhydrite 1950'

1st plug at 1950, with 50 sx cement, 2nd plug at 960' with 80 sx cement,

3rd plug at 300' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 8:20 p.m. Day: 11 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1980' with 50 sx cement,

2nd plug at 960' with 80 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

DEC 16 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

Observe this plugging.

DATE 12-16-86

Signed Jan Andrew
(TECHNICIAN)

INV. NO. 15640

12-11 FEB 10 1987

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 12 month 2 day 86 year

API Number 15-135-23,076-0002

OPERATOR: License # 6759
Name WILLIAM N. BUCKLIN III
Address 150 California Street, Ste. 300
City/State/Zip San Francisco, CA 94111
Contact Person William N. Bucklin
Phone 415-433-7100

NE 29 Twp. 18 S, Rg. 26W X West
4550
2190
(450)
Note: Locate well on Section Plat on reverse side

CONTRACTOR: License # 5302
Name Red Tiger Drilling Co.
City/State Wichita, KS 67202

Nearest lease or unit boundary line 450 feet
County Ness
Lease Name Reeves Well # 1
Ground surface elevation 2589 feet MSL
Domestic well within 350 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 200 feet
Depth to bottom of usable water 1100 feet
Surface pipe by Alternate: 1-2 X
Surface pipe planned to be set 250 feet
Conductor pipe required N/A
Projected Total Depth 4750 feet
Formation Miss

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus event...
Date 11-25-86 Signature of Operator or Agent BY RED TIGER DRILLING COMPANY Owner

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt.
This Authorization Expires 5-25-87 Approved By 11-25-86

Spud 12-3-86
Set 250' +

4550 FSL; 2190 FEL NE
Sec. 29 Twp. 18 S, Rg. 26W X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug description (e.g., 1st plug @ 280), Depth (e.g., 50 SX), and Material (e.g., 60-40 poz., 2% gel, 3% c.c.).

9:50 913-625-7821
PUSHER BRUCE FICKEL
TD 4565 FORMATION MISS
SURFACE PIPE 8 5/8 @ 258
ANHYDRITE 1950 ELEVATION 2589
STARTING TIME & DATE 12-11-86
COMPLETION TIME & DATE 8:20 PM
actual 1980 50
1st PLUG @ 1950 FT. W/ 50 SX
2nd PLUG @ 260 FT. W/ 80 SX
3rd PLUG @ 300 FT. W/ 50 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ sand - SX
CEMENT COMPANY ALLIED
TECHNICIAN S.D.
6/140 6%
Coalwood sand part.

DEC 18 1986
CONSERVATION DIVISION
Wichita, Kansas