



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Rod Randall of Silverado Wdg. has this date requested permission to plug the following described well:

Operator's Full Name: Pendleton Land & Exploration Inc.

Complete Address: 1700 Security Life Bldg Denver, Colo.

Lease Name: Matthews Well No. "B" - II

Location: 1690-SNL-100 WEL. Sec. 17 Twp. 18 Rge. 24 (E) (W)

County: Measu Total Depth: 4275 FE

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Randall was instructed to plug the well as follows:

8 5/8" 325 FE D. cur w/ 200 ST 60/40 Pozmix - 2% Gel - 3% Ca-Cl.

Reder 110 ST 30/50 Pozmix 6% Gel + 8 5/8" Plug (ENV. 2300 "B)

spot with Drill Stem - with Heavy Mud Between all Plugs

1st Plug @ 840 FE w/ 70 ST bmt.

2nd Plug @ 300 FE w/ 25 ST bmt.

3rd Plug - Solid Bridge - Halls Plug @ 40 FE 1/8 w/ 10 ST bmt.

5th In Cat Hole

Very truly yours, (By Sam Cant)

Wesley Schmidt
Conservation Division Agent

12-17-80
DEC 17 1980

CONSERVATION DIVISION
Wichita, Kansas