

15-1165-20900-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


FORM CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
200 Colorado Derby Bldg.
202 W. 1st St.
Wichita, KS 67202

Rush County Sec. 30 Twp. 16s Rge. 20 ~~XX~~/W
Location as "NE/CNW/SW" or footage from lines _____
SW/4 NW/4 SW/4

Lease Owner American Petroleum Company, Inc.
Lease Name Peer Well No. #1
Office Address 400 North Woodlawn Suite 111 Wichita, Ks
Character of Well (Completed as Oil, Gas or Dry Hole) 67208
Dry Hole



locate well correctly
on above
Section Plot

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 09-18-81
CONSERVATION DIVISION
Wichita, Ks

Date Well completed 8-23 19 81
Application for plugging filed 8-23 19 81
Application for plugging approved 8-23 19 81
Plugging commenced 6:00 P.M. 8-23 19 81
Plugging completed 7:00 P.M. 8-23 19 81
Reason for abandonment of well or producing formation No Commercial Production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Tl. Depth of Well _____
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Casing	common	0'	306.67'	8 5/8"	306.67'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1 700' with 70 sxs
Plug #2 300' with 40 sxs
Plug #3 40' with 10 sxs
5 sxs in rathole
Total - 125 sxs 50-50-pos 6% gel
P.D. @ 7:00 P.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pioneer Drilling Co, Inc.
308 West Mill Plainville, Ks 67663

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

JAMES T. BARVAIS (employee of owner) or (owner or operator) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well is filed and that the same are true and correct. So help me God.

SHEILA W. DAVIS
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Expires _____

(Signature) AMERICAN PETROLEUM COMPANY, INC.
(Address) JAMES T. BARVAIS, President
400 N. WOODLAWN SUITE 111
WICHITA, KANSAS 67208

SUBSCRIBED AND SWORN TO before me this 3RD. day of SEPTEMBER, 19 81

My commission expires June 2, 1984

Sheila W. Davis
Notary Public

W E L L L O G

OPERATOR: American Petroleum Co, Inc.

WELL NAME: Peer #1 LOCATION: SW/4 NW/4 SW/4 30-16s-20W

COUNTY: Rush STATE: Kansas

WELL COMMENCED: August 14, 1981 WELL COMPLETED: August 23, 1981

ELEVATION: 2186'K.B. TOTAL DEPTH: 4080'

PRODUCTION: D & A RIG NO: #3

CASING - 8 5/8": 8 Jts used 24# tallied @ 299.67' set @ 306.67' cemented with 175 sxs common
2 % gel 3% cc P.D. @ 11:45 P.M. 8-14-81 did circ.
5 1/2": _____

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0'	307'		307' - 1 degree	
307'	1144'	shales and sand		
1144'	1260'	red bed shale		
1260'	1471'	shale		
1471'	1499'	anhydrite		
1499'	1786'	shale		
1786'	1836'	shales		
1836'	2234'	shales	1836' - 1/2 degree	
2234'	2435'	shale and lime		
2435'	2511'	shale and lime	2511' - 1 degree	
2511'	2620'	shales		
2620'	2800'	shale and lime		
2800'	3000'	lime and shale		
3000'	3185'	lime and shale		
3185'	3360'	lime and shale		
3360'	3465'	lime and shale		
3465'	3635'	lime and shales		
3635'	3740'	lime and shale		
3740'	3833'	lime and shale		
3833'	3818'	lime and shale		
3818'	3988'	lime and shale		
3988'	4030'	lime	4030' - 2 1/2 degree	
4030'	4035'	lime and shale		
4035'	4077'	lime and shale		
4077'	4080'	lime and shale		
4080'	R.T.D.			

STAMP: SEP 21 1981
PIONEER DRILLING CO., INC.
NOTARY PUBLIC

STATE OF KANSAS
COUNTY OF

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct

PIONEER DRILLING CO., INC.
By Stacy A. Hilgus

SUBSCRIBED AND SWORN TO, BEFORE ME, This 1st day of September 1981

Judy Smith
NOTARY PUBLIC

JUDY SMITH
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires 1-5-85

W E L L L O G

OPERATOR: American Petroleum Co, Inc.

WELL NAME: Peer #1 LOCATION: SW/4 NW/4 SW/4 30-16s-20W

COUNTY: Rush STATE: Kansas

WELL COMMENCED: August 14, 1981 WELL COMPLETED: August 23, 1981

ELEVATION: 2186' K.B. TOTAL DEPTH: 4080'

PRODUCTION: D & A RIG NO: #3

CASING - 8 5/8": 8 Jts used 24# tallied @ 299.67' set @ 306.67' cemented with 175 sxs common
2 3/8 gel 3% cc P.D. @ 11:45 P.M. 8-14-81 did circ.
 5 1/2": _____

WELL MEASUREMENTS TAKEN FROM THE TOP OF EACH MEASURED:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0'	307'		307' - 1 degree	
307'	1144'	shales and sand		
1144'	1260'	red bed shale		
1260'	1471'	shale		
1471'	1499'	anhydrite		
1499'	1786'	shale		
1786'	1836'	shales		
1836'	2234'	shales	1836' - 1/2 degree	
2234'	2435'	shale and lime		
2435'	2511'	shale and lime	2511' - 1 degree	
2511'	2620'	shales		
2620'	2800'	shale and lime		
2800'	3000'	lime and shale		
3000'	3185'	lime and shale		
3185'	3360'	lime and shale		
3360'	3465'	lime and shale		
3465'	3635'	lime and shales		
3635'	3740'	lime and shale		
3740'	3833'	lime and shale		
3833'	3818'	lime and shale		
3818'	3988'	lime and shale		
3988'	4030'	lime	4030' - 2 1/2 degree	
4030'	4035'	lime and shale		
4035'	4077'	lime and shale		
4077'	4080'	lime and shale		
4080'	R.T.D.			

RECEIVED
 STATE OF KANSAS
 COMMISSION DIVISION
 Wichita, Kansas

STATE OF KANSAS
 COUNTY OF _____

The undersigned hereby certifies that the contents of this log and that the above facts are true and correct.

Glady A. Mulgrew
 1st Deputy
Judy Smith

JUDY SMITH
 NOTARY PUBLIC
 STATE OF KANSAS
 Exp. Expires / 5 31 81