


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

## WELL PLUGGING RECORD

Locate well correctly on above  
Section Plat

Rush County, Sec. 23 Twp. 16S Rge. (E) 20 (W)  
Location as "NE/CNW/SE" or footage from lines 50' NE of C NE SE NE  
Lease Owner Martion Oil Company  
Lease Name Myers "A" Well No. 1  
Office Address 1010 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed October 18, 1980 19  
Application for plugging filed October 18, 1980 19  
Application for plugging approved October 18, 1980 19  
Plugging commenced October 18, 1980 19  
Plugging completed October 18, 1980 19  
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 3900' Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged @ 750' w/60 sx. w/50/50 posmix, 6% gel.  
" " 260' w/30 sx. " " "  
" " 40' w/10 sx. " " "  
5 sx. in rathole

RECEIVED  
OCT 23 1980  
STATE CORPORATION COMMISSION  
Conservation Division  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Warrior Drilling, Inc.  
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Bill G. Lahar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. WARRIOR DRILLING INC.  
(Signature) Bill G. Lahar  
905 Century Plaza, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 1980

Marilyn Sinard  
Marilyn Sinard  
Notary Public.

My commission expires

MARILYN SINARD  
STATE NOTARY PUBLIC  
SEDGWICK COUNTY, KANSAS  
MY APPT. EXP. 4-30-83

DRILLERS LOG

October 23, 1980

#1 Myers "A"  
 50' NE of C NE SE NE  
 Sec. 23-16S-20W  
 Rush County, Kansas

OPERATOR: Martin Oil Company  
 CONTRACTOR: Warrior Drilling, Inc.  
 COMMENCED: October 10, 1980  
 COMPLETED: October 18, 1980

8 5/8" @ 260' w/150 sx.

0	263	Surface Clay
263	1320	Sand & Clay
1320	1380	Shale & Sand
1380	1419	Anhydrite
1419	2410	Shale
2410	3093	Shale & Lime
3093	3270	Lime & Shale
3270	3900	Lime
3900		RTD

D &amp; A

We certify that the above and foregoing is a true and correct copy  
 of the log on the #1 Myers "A" located in Rush County, Kansas.

WARRIOR DRILLING, INC.

*Bill G. Lahar*  
 Bill G. Lahar, Vice President

RECEIVED  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 OCT 28 1980

Subscribed and sworn to before me this 23rd day of October, 1980

MARILYN SINARD  
 STATE NOTARY PUBLIC  
 SEDGWICK COUNTY, KANSAS  
 MY APPT. EXP. 4-30-83

*Marilyn Sinard*  
 Marilyn Sinard Notary Public