

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER <sup>165</sup> ~~15-065~~-21754-0000

LEASE NAME Stephens

WELL NUMBER 1

1,915 Ft. from S Section Line

1,230 Ft. from <sup>W</sup> E Section Line

SEC. 23 TWP. 16 RGE. 20 (E) or (W) (W)

COUNTY Rush

Date Well Completed 10-14-03

Plugging Commenced 10-14-03

Plugging Completed 10-14-03

RECEIVED  
OCT 22 2003  
KCC WICHITA

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Castle Resources, Inc.

ADDRESS Box 87, Schoenchen, KS 67667

PHONE (785) 625-1555 OPERATORS LICENSE NO. 9860

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-03 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	219'	Cmtd. w/135 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each so  
Push bridge plug to 1,450', spot 50 sax cement on plug thru drill pipe. Push bridge plug to 900', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 400', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 220', spot 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor (Employee of ~~SHIELDS~~ or ~~OPERATOR~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.


(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 21st day of October, ~~2003~~ 2003

Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_





13.165-21754-0000


# Shields

Russell, Kansas

## WELL LOG

Operator: Castle Resources, Inc.  
 Well: Stephens #1  
 Commenced: October 7, 2003  
 Completed: October 14, 2003  
 Contractor: Shields Drilling Co.

Well Description: 100' SW of C N/2 SW/4  
 Sec. 23-16S-20W  
 Rush County, KS



### CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmtd. w/135 sax

Elevation: 2,140' KB

Treatment:

Production: D & A

Tops:

RECEIVED  
 OCT 22 2003  
 KCC WICHITA

..... Figures Indicate Bottom of Formations .....

Sand & shale	1,195'	
Shale	1,372'	
Anhydrite	1,409'	
Shale	2,898'	
Shale & lime	3,490'	
Lime	3,655'	
Lime & shale	3,760'	
Lime	3,892'	
Arbuckle	3,920'	RTD

Notes