

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-20,694-0000

LEASE NAME Hutchings

WELL NUMBER 1

990 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 23 TWP. 16 RGE. 20 (E) or (W)

COUNTY Rush

Date Well Completed 8/9/78

Plugging Commenced 7/8/87

Plugging Completed 7/8/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Martin Oil Producers, Inc.

ADDRESS 1010 Union Center, Wichita, KS 67202

PHONE# 316 264-0352 OPERATORS LICENSE NO. 5097

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? NO If not, is well log attached? N/A

Producing Formation Arbuckle Depth to Top 3839' Bottom 3857' T.D. 3857'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	249'	0
				5 1/2"	3848'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug - squeezed 50 sx econolite & 1 sx hulls between 8-5/8" & 5 1/2" casing. Squeezed 350# & shut in, full of cement. 2nd plug - squeezed 5 1/2" casing with 200 sx econolite cement and 3 sx hulls. Made 110 bbbls. slurry. Max pressure 1000# and was shut in at 150#, casing full. Shut in 48 hours, run measuring
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address Box 428, Hays, KS 67601

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. S. Martin, President

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]


(Address) 1010 Union Center, Wichita, KS

NOTARY PUBLIC
DIVISION
JUL 30 1987
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 87

[Signature]
Notary Public

My Commission Expires:



line to top of hard cement at 394'. Had Allied, Inc. haul 2 yards Redi-mix cement to location & fill 5 1/2" casing to surface.