

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County, Sec. 23 Twp. 16 Rge. (E) 20 (W)
Location as "NE/CNW/SE" or footage from lines NW SE SW
Lease Owner Raymond Oil Company, Inc.
Lease Name Stephens Well No. 1
Office Address 410 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-27-67 19
Application for plugging filed 9-7-67 19
Application for plugging approved 8-29-67 19
Plugging commenced 8-28-67 19
Plugging completed 8-28-67 19
Reason for abandonment of well or producing formation
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well L. Massey
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	264'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole w/ Halco. Plugged down 12:30 p.m., Plug set at 800' w/160 sx.
Plug #2 set at 240 feet w/25 sx. Plug #3 set at 40 feet w/ cement to surface.

SEP 8 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Raymond Oil Company, Inc.
Address 410 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wm. M. Raymond (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wm. M. Raymond
410 Fourth National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7 th day of September, 19 67

My commission expires 2-15-71
Ronnie Donnelly Notary Public

RAYMOND OIL COMPANY, INC.
 #1 STEPHENS
 NW SE SW Sec. 23-16S-20W
 Rush County, Kansas
 Barninger Prospect

ELEVATION: 2130 KB
 2127 DF
 2125 GL

Drilling Contractor: Company Tools Casing Record
 Date Commenced: August 16, 1967 8 5/8" @ 264' w/175 sx.
 Date Completed: August 27, 1967

Figures Indicate Bottom of Formation


<u>Formation</u>	<u>Depth</u>
Shale & Sand	263
Shale and Sand Streaks	340
Shale	670
Shale & Shells	730
Red Bed & Shale	835
Sand & Shale	1040
Shale	1632
Shale & Shells	2020
Lime & Shale	2135
Shale & Lime	2315
Lime & Shale	3340
Lime, Shale w/ Chert Streaks	3388
Lime & Shale	3525
Lime	3792
Lime, Shale & Chert	3827
Lime, Chert w/Shale Streaks	3854
Lime & Shale	3867
Lime, Shale, Chert & Sand	3870
Lime	3926
Lime & Chert	3938
TD	3938

LOG TOPS


Anhydrite	1360
Base Anhydrite	1397
Topeka	3152
Heebner	3449
Toronto	3469
Lansing	3494
Base Kansas City	3478
Marmaton	3809
Cherokee	3855
Cherokee Sand	3858
Arbuckle	3898
RTD	3934

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I hereby certify that the above and foregoing is true and correct to the best of my knowledge.


 Wm. M. Raymond

Subscribed and sworn to before me, this 7th day of September, 1967.


 Ronnie Donnelly - Notary Public

My commission expires:
February 15, 1971

RECEIVED
 SEP 8 1967
 CONSERVATION DIVISION
 Wichita, Kansas