

K-165-01909-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Rush County. Sec. 2 Twp. 16 Rge. (E) 20 (W)
Location as "NE¼NW¼SW¼" or footage from lines. Center NE SE NE
Lease Owner. Phillips Petroleum Company
Lease Name. Doerr Well No. 2
Office Address. Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed. 11-19-47 19.
Application for plugging filed. 11-20-47 19.
Application for plugging approved. 11-19-47 (Verbal) 19.
Plugging commenced. 11-19-47 19.
Plugging completed. 11-19-47 19.
Reason for abandonment of well or producing formation Dry Hole

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr
Producing formation. None Depth to top. Bottom. Total Depth of Well. 3795 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite	Dry	1328'		8 5/8"	1368	None
Lansing Kansas City	Dry	3406'				
Conglomerate	Dry	3694'				
Quartzite	Dry	3751'				
Granite	Dry	3765'				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled hole with heavy mud from 3795' to 1365'. Ran 15 sacks of cement at 1365'. Filled with heavy mud to 250'. Ran 10 sacks of cement at 250'. Filled with heavy mud to 20'. Ran 10 sacks of cement in filling to base of cellar.

JUL 27 1948

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Ralph McKnight
Address. Box 528 Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Ralph McKnight (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph McKnight
Box 528 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of July 1948.

My commission expires June 14, 1952 Notary Public.

FILE 2 16 20W
LOG 148

15-165-01909-0000

Form No. 873

Formation Record

Lease Doerr

Well No. 2

FROM	TO	Formation	REMARKS
0	280	Shale, Shell, and Sand	ELEVATION: 2123.40' R.T.B.
280	565	Shale and Shells	2120.90' D.F.
565	700	Lime and Shale	
700	1060	Shale, Sand, Shells, Red Bed	2118.00' Ground
1060	1100	Shale and Shells	
1100	1200	Red Bed and Shale	
1200	1310	Red Bed, Shale, and Shells	
1310	1378	Shale and Anhydrite	Top Anhydrite @ 1328'
1378	1400	Red Bed and Shale	
1400	1810	Red Bed, Sand, and Shale	
1810	1980	Lime, Shale, and Salt	
1980	2070	Lime and Shale	
2070	2175	Lime and Sandy Shale	
2175	3492	Lime and Shale	Top L.K.C. 3406'
3492	3694	Lime	
3694	3706	Conglomerate	Top Conglomerate 3694'
3706	3731	Shale, Chert, Conglomerate	
3731	3740	Shale and Chert	
3740	3748	Chert and Conglomerate	
3748	3751	Conglomerate, Chert, and Lime	
3751	3768	Quartzite	Top Quartzite 3751' Granite 3765'
3768	3795	Granite	

PLEISTOCENE
 FILE SEC 2 T 16 R 20W
 BOOK PAGE 148 LINE 42